HAMPTON





CAMBRIDGE CONSTRUCTION: Full overlay, hardwood construction with premium MDF painted doors. Soft-close doors and drawers. EuroBox plywood drawers with five-piece drawer fronts.



www.RiverRunCabinetry.com

RiverRun Cabinet Construction





I-BEAM STRETCHERS

All base cabinets have a 3/8" x 3" I-beam stretcher on the top left and right sides. The stretchers are captured by grooves in the frame, end panels and back panel to provide reinforcement to the base cabinet construction.

A) FACE FRAMES

Constructed from $\frac{34''}{2}$ hardwoods. Base and wall frames have $\frac{112''}{2}$ stiles and rails. Base cabinets have a 1'' reveal at the top. Bottom and sides have $\frac{14''}{2}$ reveal.

(B) DOORS

Premium full overlay door styles with softclose door hinges. Stained doors are solid hardwood and painted doors are MDF. (See door specification pages: SF6-8 for details.)

C PANELS

Constructed from ½" plywood with option for finished skins. Ends, tops and bottoms are captured in frame grooves. Backs are captured in end panel grooves.

(D) HINGES

6-way fully concealed 108° self-closing cup hinges that allow easy height, width, and depth adjustment are standard.

(E) CABINET INTERIOR

Sealed with clear-coat finish. Finished Interior* option may be selected on wall, base and tall cabinets up to 24" deep.

F BACKS

Backs are solid 1/2" plywood. Base cabinet backs extend to the floor providing optional structural stability.

G DRAWERS

EuroBoxes are 5/8" thick hardwood plywood with dowel construction. Option to upgrade to dovetail construction. Both options are clear coated and bottoms are fully captured plywood. Glides are under mount, full extension soft-close.

(H) TOE KICKS

Constructed from $\frac{1}{2}$ " unfinished plywood. They are inset into the cabinet box $\frac{3}{2}$ " and are $\frac{4}{2}$ " high. Toe Kick Material (TKS) required to finish the toe kick space.

(I) ROLL OUT TRAY & PILASTER KIT (optional)

EuroBox (standard) or dovetail upgrade option for roll out tray box with undermount glides. Pilasters are installed at each corner of base cabinet (pantries get 2 sets of pilaster kits) with slots for approximate 1" height adjustments.